




Asset Management Working Group

Duro Basic (TfL)
Bhavin Shah (FSW)



AMWG Objectives

- Develop and promote good practice in the management of Bridge Infrastructure in London
- Collaborative research approach
- Meets every 6 weeks




2021/22 Updates

- Good practice guides
 - Risk Based Inspections (GI and PI)
 - Defect codes Update
 - Consistent Inventory Data
- Life cycle/Investment planning
- Consistent Element Hierarchy for
 - Tunnels, Buildings, River Piers
- Mobile Inspection



Risk Based Inspections



- Optimal allocation of resources
- Balance between Risk and Inspection efforts
- Proactive Approach



Inspection and Maintenance Planning strategies





Figure 1: Evolution of Inspection and Maintenance Planning Strategies




BPRN Inspections (810 Structures)




BPRN Inspections

Structures with No
Inspections in Last 6 Years




Structures with No PI in Last
6 Years




BridgeStation RBI Module


Critical Risk/Reduce PI Interval



Low Risk/Increase PI Interval



Structure Count By Risk Category
(Time Based Regime)



BridgeStation RBI Module

Maintaining Area	Analysis Type	Notes	Added to Programme	Start Year		
				Total PI	Total GI	Annual Cost
All	Time Based PI & GI		No	179	94	£0
All	Risk Based PI & Time Based GI		No	137	138	£0
All	Risk Based PI & GI		No	116	146	£0
All	Altered		No	116	146	£0




Defect Code Updates

No.	Item	Severity		
		1	2	3
20	Aesthetic Issues (possibly affecting durability e.g. algae, lichen, moss, leachate, efflorescence, staining, etc)	.1 None, Low or Medium levels of aesthetic issues not visible to the public. Not significant to long term durability.	High levels of aesthetic issues not visible to public and/or low levels visible to the public. Not significant to long term durability.	High levels of aesthetic issues in areas with low to moderate footfall. Affecting long term durability.
21	Pigeon proofing/ Guano	.1 None, insignificant defect to the pigeon proofing, insignificant deposits of guano	Missing spikes, small breaks in the mesh/netting or gaps at connections. Guano build up not noticeable by public but could affect durability of element.	Missing spikes and evidence of guano, breaks in netting large enough to allow avian access. Guano build up noticeable by the public.
22	FRP Composites Pultruded and Moulded construction	.1 No sign of damage	Minor signs of damage	Moderate signs of damage
		.2 No visible signs of open joints	Joints open slightly on surface or cracked coating at joints	Open joints <50% width of beam in areas of low flexure or <25% in areas of high flexure
		.3 No signs of rusting or damage to fixings	Non-structural bolts loose, minor corrosion of fixings	Non-structural bolts missing, moderate corrosion of fixings
		.4 No signs of damage to bonded joints	Minor signs of disbondment at joints	Bonded joints failing in areas of low flexure



- New defect codes
 - Joint types
 - Pigeon proofing/ Guano
 - FRP Composites Pultruded and Moulded construction
 - Aesthetic Issues
 - Composite Structures




Consistent Inventory Data GPG



Mobile App for Inspection




App Usage



Mobile Inspection

Key Features

- Offline
- Previous inspection photos/comments while onsite
- Interactive defect code table
- Manage inspection teams
- Risk assessment forms



Life cycle Planning


LoBEG Good Practice Guide

Lifecycle Planning for Highway Structures

Version 2.0
August 2011



London Bridges
Engineering Group



Investment Strategies

- National Strategies and Rates/SAVI
- Custom London Strategies and Rates
- Optimisation




Figure 2: Balancing Risk, Performance, Cost and Interventions



BridgeStation

Automate Stock Investment Planning

Investment Planning : Standard Scenarios

Note: Following investment scenarios are based on each strategy defined in the strategies section.

Standard (System Managed) Scenarios

#	Title	Strategy	Start Year	Optim. Step	Whole Life Cost	Structure Count	Stock BCI Avg		
							Yr 0	Yr 5	Yr 10
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

▼ National Strategy

View Report	Do Nothing	Do Nothing	2021			3205	86.16	78.53	68.98
View Report	Planned Preventative	Planned Preventative	2021		£3,432,022,128	3205	86.16	90.74	87.69
View Report	Planned Targeted	Planned Targeted	2021		£3,454,174,151	3205	86.16	90.30	86.94
View Report	Planned Do Minimum	Planned Do Minimum	2021		£4,484,926,187	3205	86.16	86.31	80.42
View Report	Unplanned Reactive	Unplanned Reactive	2021		£4,480,523,857	3205	86.16	86.18	80.29

▼ National Strategy - Optimised




Option Analysis


☒ Expenditure
 ☒ BCI Avg
 ☐ BCI Critical
 ☐ SOGR
 ☐ Works (No)
 ☐ Works (Area)
 ☐ Structures At Risk

Export Chart

Export Data



Whole life cost




Year	BCI Average	BCI Critical	Expenditure	SOGR %	Structures with Safety or Performance at Risk	Works	Area	Area %	Structure Count
Scenario Title: Planned Do Minimum - Optimised (Option 2) (Continued on the next page)									

Scenario Title	Chart Title	Strategy Name	Whole Life Cost
Planned Preventative - Optimised (5 Yrs)	Option 1	Planned Preventative	£3,329,228,047
Planned Do Minimum - Optimised	Option 2	Planned Do Minimum	£4,409,685,474



Visualise Data Over Map



Detail Forward work plan

Life Cycle Plans (SAMPT): Planned Preventative

Back (LCP Admin)

Maintenance Strategy: Planned Preventative

Start Year: 2021

Date Created: 25/11/2021

SSCI Average By Type

SSCI Critical By Type

Expenditure Summary by Element

Expenditure by Type

Work, Shortfall & Condition

Condition Bands

Fwd programme of works (year view)

Fwd programme of works (list view)

Life Cycle Plans (individual structures)

Export

Optimise LCP

Refresh Data

Show condition profile

Filter: Years :

Note: Click on blue cell to view/add works | Key: Add

#	#	Structure Name	Structure Type	Whole Life Cost	2021/22	2022/23	2023/24	2024/25	2025/26	2026/27	2027/28	2028/29	2029/30	2030/31	2031/32
	View	New Bridge	Bridge	£505 k		£164k				£50k					
	View	Bliss Road Tunnel	Culvert	£491 k		£78k	£36k								
	View	Barnet Road Tunnel	Culvert	£161 k		£25k									
	View	Longbridge Road Tunnel	Culvert	£296 k		£849							£46k		
	View	Barnet Road Tunnel	Culvert	£504 k		£76k									
	View	Longbridge Road Tunnel	Retaining Wall	£11 k		£4k									
	View	Longbridge Bridge	Bridge	£532 k		£5k				£82k					
	View	New Bridge Road Bridge	Pedestrian Subway (or Underpass)	£685 k		£80k					£35		£44k		
	View	Longbridge Road Tunnel	Retaining Wall	£680 k		£69k				£3k					
	View	Longbridge Road Tunnel	Pedestrian Subway (or Underpass)	£574 k		£100k									£2
	View	Longbridge Road Tunnel	Retaining Wall	£895 k						£3k					
	View	Longbridge Bridge	Bridge	£485 k		£229k									
	View	Bliss Road Tunnel &	Culvert	£219 k		£6k	£34k			£7					
	View	Longbridge Road Tunnel	Pedestrian Subway (or Underpass)	£289 k		£85k									£1
					£269m	£70m	£18m	£21m	£47m	£1m	£32m	£56m	£10m	£1	



Ongoing Topics

- Scour - Hidden Defects
- Net Zero
- Inspection Brief
- Investment Strategies and Life Cycle Planning



Questions

